National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name : TESTING LAB, BHAGWATI PRODUCTS LTD, SP1-1, INDUSTRIAL AREA KAROLI, TAPUKARA EXTN, ALWAR, BHIWADI, RAJASTHAN, INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-9513 **Page No** 1 of 1

Validity 10/05/2021 to 09/05/2023 **Last Amended on** -

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
Permanent Facility				
1	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Split Air Conditioner	Maximum Operating Condition Test	IS 1391 (Part 2, Cl 9.4)
2	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Split Air Conditioner	Power Consumption Test for cooling	IS1391(Part2, Cl 9.7)
3	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Split Air Conditioners	Cooling Capacity Test	IS 1391-Part 2 , Cl. 9.9
4	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Split Air Conditioners	Enclosure Sweat	IS 1391 (Part 2, Cl 9.6)
5	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Split Air Conditioners	Freeze-Up Test	IS 1391(Part 2 Cl 9.5)
6	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Window Air Conditioner	Cooling Capacity Test	IS 1391(Part1, Cl. 10.10)
7	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Window Air Conditioner	Maximum Operating Condition Test	IS 1391(Part1 , Cl.10.4))
8	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Window Air Conditioner	Power Consumption Test for Cooling	1391 (Part 1, Clause 10.8)
9	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Window Air Conditioners	Enclosure Sweat Test	IS 1391(Part1 , Cl.10.6)
10	MECHANICAL- HEATING, VENTILATING, AND AIR CONDITIONING(HVAC)	Window Air Conditioners	Freeze Up Test	IS 1391(Part1 , Cl.10.5)